

## MODELO DE ANALISIS CON ITBIS TRANSPARENTADO

DESCRIPCION	CANT	UND	PU	ITBIS	SUBTOTAL	SUBTOTAL ITBIS	TOTAL
<b>ZAPATAS MUROS 6" 0.45m x 0.25m HORMIGON INDUSTRIAL 180Kg/cm2</b>	<b>1.00</b>	<b>M3</b>			<b>RD\$8,166.64</b>	<b>RD\$1,297.40</b>	<b>RD\$9,464.04</b>
Zapatras Muros 6" 3 $\phi$ 3/8" y 3/8" @ 0.25m							
<i>Volumen Análisis</i>	1.00	M3					
<i>Materiales y Equipos</i>							
Acero - Cuantía QQ/M3	0.71	QQ	RD\$1,992.37	RD\$358.63	RD\$1,414.58	RD\$254.63	
Hormigon Industrial 210 Kg/cm2 + 10% desp.	1.10	M3	RD\$5,211.86	RD\$938.13	RD\$5,733.05	RD\$1,031.94	
Alambre Dulce No. 18	1.42	LB	RD\$42.37	RD\$7.63	RD\$60.17	RD\$10.83	
<i>Mano de Obra</i>							
Mano de Obra Acero	8.89	ML	RD\$107.87	RD\$0.00	RD\$958.84	RD\$0.00	
Total/UND					RD\$8,166.64	RD\$1,297.40	RD\$9,464.04